

Peacham, VT

Town Hall Renovation

Addendum 2 Incorporate the following changes into the construction documents.

April 23, 2025

1. Electrical

- a. For each Restroom provide the following heaters:
 - i. AMIR Mirage Convactor AMIR0501, 500-watt, wall-mounted, anodized aluminum paint finish.
- b. Eliminate the dimmer switch leg for L-3 and L-4 lighting fixtures in HALL 1.

2. Lighting

- a. The 2x2 Alcon lighting fixtures have switches for three possible wattages--20W, 25W, or 30W. At installation, set the fixtures at 30W. It may be necessary to adjust some of the wattages depending on light levels. Color temperature should be 3500K.

3. Excavated Area Between Ramp Walls

- a. For fill between the ramp side walls, crushed granite or crushed ledge are acceptable.